



बढैयाताल गाँउपालिका
गाँउ कार्यपालिकाको कार्यालय
मैनापोखर, बर्दिय
लुम्बिनी प्रदेश, नेपाल
(योजना शाखा)

०८४-४०९०७७

पत्र संख्या :- ०८०/०८१

सिलबन्दि दर भाउपत्र पेश गर्ने सम्बन्धि सूचना
पहिलो पटक प्रकाशित मिति : २०८०/१२/०९

उपरोक्त सम्बन्धमा तपसिलको कार्यहरु सिलबन्दि दरभाउपत्रको माध्यमबाट गराउनु पर्ने भएकाले यस कार्यालयमा आ.ब. ०८०/०८१ का लागि मौजुदा सूचीमा दर्ता रहेका फर्महरुबाट निम्न लिखित कागजात सहित सूचना प्रकाशित मितिले ७ (सात) औं दिन कार्यालय समय सम्ममा रित पूर्वक सिलबन्दि दरभाउ पत्र फारम पेश गर्नु हुन जाकारीका लागि यो सूचना प्रकाशित गरिएको छ ।

पेश गर्नु पर्ने कागजातहरु :

१. आ.ब. ०८०/०८१ सम्मको नबिकरण गरेको इजाजत-पत्रको प्रतिलिपि.....१
 २. मुल्य अभिवृद्धि कर दर्ता प्रमाण-पत्रको प्रतिलिपि.....१
 ३. कर चुक्ता प्रमाण-पत्रको प्रतिलिपि१
 ४. यस कार्यालयबाट जारी दरभाउ-पत्र फारम.....१
- गर्नु पर्ने कार्यहरु

Contract ID No.

Name of the Project:- Boundary Wall construction at 1No. Ward office

Name of the place :- Badhaiyatal Rural Municipality ward No 1

Name of the work:- PCC, RCC, Brick Masonry, Grill Works.

F.Y.:- 080/081

S.N.	Description	Unit	Quantity	Rate (Rs)		Amount in fig. (NRs.)
				In fig.	In words	
Provisional Sum						
1	provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfillingetc all complete as per DoR Standard Specification for Road and Bridge Works	Pcs	1.00			
2	Carry out Lab tests for material and works as required and instructed by the Engineer. [SP 5]	Pcs	1.00			
Civil Works						
1	EarthWork					
1.1	Excavation of foundation of structures in all types of soil/rock, including construction of shoring and bracing, removal of stumps and other deleterious matter (Buy Manual Means) and backfilling with approved material as per drawing & technical specifications. [Detailed Specifications Of Building Works (Civil) 11B (B1-B7)]	cum	18.19			
1.2	Earth filling in Foundation trench in 15cm layer with sprinkling water as per specification & instruction of site engineer. [Detailed Specifications Of Building Works (Civil) 11B(B2, B3, B5, B6)]	cum	9.10			
2	Soling Work					
2.1	Flat Brick soling work in foundation with supplying of approved quality of Stone, laying, ramming and levelling including filling in the joints with sand as per design, drawing and specification. [Detailed Specifications Of Building Works (Civil) 11H16-H18]	Sqm	28.12			
3	PCC Works					
3.1	Foundation and wall with cement concrete of 1:2:4 including supplying of materials and hauling upto 30m. [Detailed Specifications Of Building Works (Civil) 11D]	cum	2.80			
3.2	PCC for RCC Foundation and wall with cement concrete of M20 including supplying of materials and hauling upto 30m. [Detailed Specifications Of Building Works (Civil) 11D]	cum	8.73			
4	Reinforcement Work					
4.1	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications [Detailed Specifications Of Building Works (Civil) 11D9]	Kg	1027.96			
5	Brickwork					
5.1	Machine Made Brick masonry work in 1:4 c/s mortar including material, labour required for mixing placing curing and all complete work as per drawing and specification [Detailed Specifications Of Building Works (Civil) 11C1]	cum	15.49			
6	PLASTERING WORKS					
6.1	12.5mm Cement sand plastering on walls etc. in perfect line and level with top quality finish including necessary scaffolding, raking the joint, wetting	Sqm	57.02			

Website:badhaiyatalmun.gov.np

Email:badhaiyatal2073@gmail.com

अनुमोदित
मुख्य प्रशासकीय अधिकारी



बढैयाताल गाँउपालिका
गाँउ कार्यपालिकाको कार्यालय
मैनापोखर, बर्दिय
लुम्बिनी प्रदेश, नेपाल
(योजना शाखा)

००४-४०१०७७

पत्र संख्या :- ०८०/०८१

	the surfaces and curing the plastered surfaces all complete on 1:4 c/s mortar. [Detailed Specifications Of Building Works (Civil) 11I]				
6.2	Flush cement pointing works in 1:2 C/s mortar on walls etc in perfect line and level with top quality finish including necessary scaffolding, raking the joint, wetting the surfaces and curing the pointed surfaces all complete (SP 11I)	Sqm	81.60		
7	PAINTING WORKS				
7.1	Two Coats of Plastic Emulsion Paint on plastered Surface [Detailed Specifications Of Building Works (Civil) 11J]	Sqm	57.02		
7.2	Two coat primer, Two coat Enamel paint and all complete work as per drawing and specification [Detailed Specifications Of Building Works (Civil)]	Sqm	33.58		
8	Grill works				
8.1	MS pipe, MS Angle, MS Grill; Heavy Quality- Buying, supplying, cutting, bending, fixing in position and all complete work as per drawing and specification [Detailed Specifications Of Building Works (Civil) 11M, 11J]	Kg	1110.03		
9	Formworks				
9.1	Waterproof plywood formwork including buying, supplying, cutting, fixing and all complete work as per drawing and specification [Detailed Specifications Of Building Works (Civil) 11.E]	Sqm	118.15		
	Sub Total Amount				
	Ps Amout				
	Total Amout Without Ps				
	Add VAT @ 13%				
	Contingency @3%				
	Grand Total Amount				

अर्जुन सुवेदी
प्रमुख प्रशासकीय अधिकृत