



वढैयाताल गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय

०८५-४०१०७७

मैनापोखर, बर्दिया, लुम्बिनी प्रदेश, नेपाल
Office of the Rural Municipal Executive
Mainapokhar, Bardiya, Lumbini Province, Nepal

प.स.: २०८२/८३

सिलबन्दी दरभाउपत्र पेश गर्ने सम्बन्धि सूचना

प्रथम पटक सूचना प्रकाशित मिति: २०८२/१२/०१

उपरोक्त सम्बन्धमा तपसिलको कार्यहरु सार्वजनिक खरिद नियमावलीको नियम ८५ 'क' बमोजिम गराउनु पर्ने भएकाले यस कार्यालयमा आ.व. ०८२/०८३ का लागि मौजुदा सुचिमा दर्ता रहेका फर्महरुबाट निम्नलिखित कागजात सहित सूचना प्रकाशित मितिले ७(सात) औं दिन कार्यालय समय सम्ममा रितपूर्वक तपशिल बमोजिमको नारम (BOQ) भरि पेश गर्न हुन जानकारीका लागि यो सूचना प्रकाशित गरिएको छ।

पेश गर्नु पर्ने कागजात हरु:

१. आ.व. ०८२/०८३ सम्मको नविकरण गरेको ईजाजत पत्रको प्रतिलिपि १
२. मूल्य अभिवृद्धि कर दर्ता प्रमाणपत्रको प्रतिलिपि..... १
३. कर चुक्ता प्रमाणपत्रको प्रतिलिपि..... १
४. यस कार्यालय बाट जारी फारम (BOQ)..... १

गर्नुपर्ने कार्यहरु(BOQ)

Name of the project: विभिन्न स्थानमा ग्राभेल सडक निर्माण

Location: Badhaiyat ward no 2

Name of the Work: Construction and Maintainance of Gravel Road

f/y:2082/083

S.No.	Description of works	Unit	Quantity	Rate (Rs.)		Amount
				in Numbers	In Words	
General						
1.00	Provide and installation of Project information Board 0.9m*1.2m	nos	1.00	3000.00	Three Thousand Only	3000.00
2.00	Provide Camber Rod (Either Made of MS Angle OR Wooden Plank) For Maintaining Camber & Superelevation, including All Complete Work as per Drawing & technical Specification.	nos	1.00	5000.00	Five Thousand Only	5000.00
				Total (PS)		8000.00
Roadworks						


अञ्जित धार
प्रमुख प्रशासकिय अधिकृत



बढैयाताल गाउँपालिका

गाउँ कार्यपालिकाको कार्यालय

मैनापोखर, बर्दिया, लुम्बिनी प्रदेश, नेपाल

Office of the Rural Municipal Executive

Mainapokhar, Bardiya, Lumbini Province, Nepal

०८५-४०१०७७



1.00	Loosening, levelling, and compacting original ground supporting Subbase to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification (compacting original ground supporting embankment)	Sqm	1130.00		
2.00	Providing, laying, spreading, watering and compacting embankment with borrow material in layers not exceeding 150mm including haulage as per drawing and Technical Specifications. (Mechanical Means)	Cum	54.73		
3.00	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications. (SP 1201)	Cum	169.50		
4.00	Roadway Excavation in all type of soil/rock and Formation of Embankment with Material Deposited from Roadway Excavation: Providing, laying, spreading and as per Drawing and Technical Specification	Cum	36.00		
			Sub Total Amount		
			PS Amount		
			Amount Without PS		
			Vat @13%		
			Total Amount		

In Words Rs.:


Name of Firm:

Address: -

Name of the representative:

Signature:

Date:


अर्जुन थारु

प्रमुख प्रशासकीय अधिकृत

अर्जुन थारु
प्रमुख प्रशासकीय अधिकृत