



बढैयाताल गाँउपालिका
गाँउ कार्यपालिकाको कार्यालय
मैनापोखर, बर्दिय
लुम्बिनी प्रदेश, नेपाल
(योजना शाखा)

००४-४०१०७७

पत्र संख्या :- ०८२/०८३

सिलबन्दि दर भाउपत्र पेश गर्ने सम्बन्धि सूचना
दोस्रो पटक प्रकाशित मिति : २०८२/०७/२७

उपरोक्त सम्बन्धमा तपसिलको कार्यहरु सिलबन्दि दरभाउपत्रको सूचनाबाट गराउनु पर्ने भएकाले यस कार्यालयमा आ.ब. ०८२/०८३ का लागि मौजुदा सूचीमा दर्ता रहेका फर्महरुबाट निम्न लिखित कार्यालय सहित सूचना प्रकाशित मितिले ७ (सात)औं दिन कार्यालय समय सम्ममा रित पूर्वक सिलबन्दि दरभाउ पत्र फारम पेश गर्नु हुन नपकारीका लागि यो सूचना प्रकाशित गरिएको छ ।

पेश गर्नु पर्ने कागजातहरु :

१. आ.ब. ०८२/०८३ सम्मको नबिकरण गरेको इजाजत-पत्रको प्रतिलिपि.....१
२. मुल्य अभिवृद्धि कर दर्ता प्रमाण-पत्रको प्रतिलिपि.....१
३. कर चुक्ता प्रमाण-पत्रको प्रतिलिपि१
४. यस कार्यालयबाट जारी दरभाउ-पत्र फारम.....१

गर्नु पर्ने कार्यहरु

Contract ID No.


Name of the Project:- ०६ नं वडा कार्यालय हातमा शौचालय, गेट निर्माण, माटो पटानी तथा बालु बिछ्याउने, किचन व्यवस्थापन र मन्दिर मर्मत तथा रंगरोगन

Name of The Place:- Badhaiyatal Rural Municipality Ward No-06 ,Bardiya

Name of The Work:-Construction of toilet,soil filling,interlocking concrete blocks, and gate works

F.Y.:
2082/083

S.N.	Description	Unit	Quantity	Rate (Rs)		Amount in fig. (NRs.)
				In fig.	In words	
	PART 01: GENERAL AND PROVISIONAL SUM					
1	Making & supply of hording board including making,wording painting,transportation & erection in position all complete	Ps	1.00	3000.00	Three Thuosand Only	3000.00
2	UV Disinfection Water Purifier Electric Filter, Dimention:- 420(W)x350(D)x750(H), Tank capacity- 12Ltr, Flow rate-12-15 Ltr/HR, With one year warranty.	Ps	1.00	20000.00	Twenty Thuosand Only	20000.00
	Total PS			23000.00		23000.00
	PART 02: CIVIL WORKS					
1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material including dewatering, relevant lift and disposal all complete as drawings and technical specifications. [SS/SP 907]	Cum	7.81			
2	Earth Back filling in Foundation trench in 15cm layer with sprinkling water as per specification & instruction of site engineer. [Detailed Specifications Of Building Works (Civil) 11B(B2, B3, B5, B6)]	Cum	4.69			
3	Stone soling work in foundation with supplying of approved quality of Stone, laying, ramming and levelling including filling in the joints with sand as per design, drawing and specification. [Detailed Specifications Of Building Works (Civil) 11H16-H18]	Sqm	1.51			
4	Providing and placing M15 cement concrete in foundation including compaction, curing, testing, formwork etc. all complete as per specification. [SS/SP 2000]	cum	0.88			



अर्जुन भारु
प्रशासकिय अधिकृत

अर्जुन शार
प्रमुख प्रशासकिय अधिकृत



बढैयाताल गाँउपालिका
गाँउ कार्यपालिकाको कार्यालय
मैनापोखर, बर्दिय
लुम्बिनी प्रदेश, नेपाल
(योजना शाखा)

००८४-४०९०७७

पत्र संख्या :- ०८२/०८३

5	PCC for RCC Foundation and wall with cement concrete of M20 including supplying of materials and hauling upto 30m. [Detailed Specifications Of Building Works (Civil) 11D]	cum	3.49		
6	Providing and laying Brick Masonry work in cement mortar 1:4 in structure excluding pointing and plastering works and providing necessary as per Drawing and Technical Specifications (SS/SP 2500)	cum	8.30		
7	Providing and applying 12.5mm thick plaster with cement mortar 1:4 on brick work in structure as per Technical Specifications (SS/SP 2500)	sqm	102.59		
8	38mm thick (1:2:4) P.C.C. for flooring with approved quality of O.P.C. cement, sand and crushed stone aggregate including mixing, laying, punning, rubbing in hard surface curing etc all complete as per instruction of site Engineer. (Sp. Item. 11H, H1)	m2	14.25		
9	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS/SP 2014)	Mt	344.43		
10	MS pipe, MS Angle, MS Grill, MS Sheet, MS Plate Works; Heavy Quality- Buying, supplying, cutting, bending, fixing in position including one coat primer, Two coat Enamel paint and all complete work as per drawing and specification. (Sp. Item. 11M, M1-M5, M6, M8, M11)	kg	722.67		
11	Two Coats of Plastic Emulsion Paint on plastered Surface [Detailed Specifications Of Building Works (Civil) 11J]	sqm	203.65		
12	Providing, Preparing and Installing form work including necessary supports and removing after completion for walls vertical plain surface. (Height upto 3 m) (SS/SP 1804,1805)	sqm	29.13		
13	20mm cpvc pipe supplying laying fitting all complete	Rm	20.00		
14	PVC Pipe 110mm 4kg laying fitting all complete	Rm	20.00		
15	110 mm T (with door)	Pcs	1.00		
16	110 mm y (with door)	Pcs	1.00		
17	110 mm 90 degree	Pcs	2.00		
18	110 mm 45 degree	Pcs	2.00		
19	PVC Pipe 75mm 4kg laying fitting all complete	Rm	35.00		
20	75 mm T (with door)	Pcs	2.00		
21	75 mm y (with door)	Pcs	1.00		
22	75 mm 90 degree	Pcs	4.00		
23	16 mm HDP PIPE	Kg	5.00		
24	15(1/2") mm GI nipple	nos	1.00		
25	15(1/2" x 4") mm GI nipple	nos	3.00		
26	15mm pillar cock	Pcs	2.00		
27	15mm Angle cock	Pcs	2.00		
28	15mm pvc Connection Pipe	Pcs	2.00		
29	Pan set (21Inch)	Set	1.00		
30	15mm Bibcock shortneck	nos	1.00		
31	20"x16" wash basin	Pcs	2.00		
32	1000L HDP water storage tank(N-S 353)	nos	1.00		
33	Porcelain glazed tile work in floor	sqm	3.86		
34	Porcelain glazed tile work in wall	sqm	4.20		
35	20"x16" looking mirror	set	1.00		



बढैयाताल गाँउपालिका
गाँउ कार्यपालिकाको कार्यालय
मैनापोखर, बर्दिय
लुम्बिनी प्रदेश, नेपाल
(योजना शाखा)

०८४-४०९०७७

पत्र संख्या :- ०८२/०८३

36	25mm cpvc pipe	Rm	10.00		
37	20mm cpvc pipe	Rm	15.00		
38	25mm cpvc 90 degree elbow	Pcs	2.00		
39	25mm cpvc T	Pcs	2.00		
40	25mm cpvc union	Pcs	1.00		
41	25mm bulb valve	Pcs	1.00		
42	20mm Tank nipple	Pcs	1.00		
43	25mm Tank nipple	Pcs	1.00		
44	Elbow 90 degree (20 mm)	rm	4.00		
45	Equal Tee (20 mm)	Pcs	6.00		
46	Couplen Socket (20 mm)	Pcs	3.00		
47	20 mm female brass tee	Pcs	2.00		
48	20 mm female elbow brass	Pcs	6.00		
49	20 mm union	Pcs	1.00		
50	20 mm end plug	Pcs	8.00		
51	118 ml cpvc solvent	Pcs	1.00		
52	20 mm metal clip	Pcs	6.00		
53	Installation of 2.5 sq mm N.S. Certified Copper Wire light/Fan point wiring work using good quality of PVC pipe .concealed wiring work.It includes cost of Wire, Pipe, Switch, Switch Board, Ceiling rose/Fan Box, Junction Board, box, Labour Cost & and other required material all complete work for a Point as Per Engineer Instruction.	Point	5.00		
54	LED Bulb (5 Watt)	No	2.00		
55	Miscellaneous item	Ls	1.00		
56	Steel Kitchen Sink 18" medium type	No	1.00		
57	15mm Bibcock longneck	No	1.00		
58	40mm kitchen waste pipe	No	1.00		
59	Providing, laying, spreading, watering and compacting embankment with borrow material in layers not exceeding 150mm including haulage as per drawing and Technical Specifications. (Mechanical Means)	Cum	45.27		
60	After providing the materials, the task involves laying 60 mm thick heavy-duty interlocking concrete blocks on top of a 50 mm thick layer of crusher work.	sqm	80.00		
Sub Total Amount					
PS					
Total Without PS					
VAT 13 %					
Grand Total cost NRs.					

In words Rs :-

Name of firm :-

Address :-

Firm's Seal :-

Name of the representative :-

Signature :-

Date :-

[Signature]
अर्जुन थारु
प्रमुख प्रशासकिय अधिकृत